(*b*) That the purchaser shall not cut bamboos outside the limits of the block to which the lease refers and not exploit immature clumps less than three years old.

(*c*) That the lessee will be personally responsible for the acts of his agents, servants, or coolies employed in the cutting, collection and removal of bamboos and for preventing the cutting of clumps under two years by himself, his agents, servants or coolies.

(*d*) That he shall not sublet the contract to anybody or appoint any agent to work for him except with the written sanction of the District Forest Officer.

(*e*) That he shall have no right whatsoever over the block and over the bamboos paid for but left unremoved in any of the blocks after the 31st December 1929.

(*f*) That he shall accept the minimum quantity fixed in the notification as available in the block concerned and shall have no claim on the department for any dificit that may be found. If he removes any quantity above the minimum fixed with the lease period he shall pay for the excess quantity at auction sale rates.

(*g*) That he shall abide by such orders as the District Forest Officer may issue regulating the transport of bamboos to and collection at their rafting stations.

(*h*) That he shall abide by the rules of the department as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*i*) That he or his men shall not enter the forest after sunset and before sunrise.

(*j*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of bamboos removed and shall keep it open for the examination of Forest Officers above the grade of guards.

(*k*) That he understands that the sale does not prohibit the issue of retail licenses at seigniorage rates or the exercise by the villagers of their rights in the Forests.

(*l*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of the cancellation of contract, enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

K. REVANNA,
District Forest Officer.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Notice dated 26th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 19th February 1929, for restoring Alambadi Nagalkere Tank, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Alambadi Nagalkere Tank, Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate rate will not be accepted.

Abstract estimate of the cost of Restoring Alambadi Nagalkere of Malur Taluk :—

No.	Items of work	Per	Quantity	Rate	Cost	Total
	Bund.			Rs.	Rs.	Rs.
1	Earthwork with watering and tamping including lead and lift.	C.yds.	6,883			
2	Turfing	S.yds.	6,006			
3	Removing and resetting old stone work wherever necessary.	Lump	sum			
4	New stone work ...	C.yds.	885			
5	Fixing grade stones including figuring and painting.	No.	30			
6	Fixing Index stones including figuring and painting.	,,	30			
7	Fixing Register No. Stone including figuring and painting.	,,	1			
8	Fixing B. M. Stones including figuring and painting.	,,	2			
9	Fixing gauge stones including figuring and painting.	,,	1			
10	Jungle clearing	Lump	sum			
11	Cutting grips and clearing ant hills, etc....	Lump	sum			
	Total to Bund ...	...	..	...	...	...
	Sluice No. I at R. L. 45·00.					
1	Earthwork excavation	C.yds.	49			
2	Do refilling	,,	54			
3	Concrete in surki mortar	C.ft.	107			
4	Burnt brick in surki mortar	,,	509			
5	Burnt stone slabs	S.ft.	239			
6	Surki mortar plastering	Sqrs.	6·36			
7	Drilling holes in cross and orifice slabs ...	No.	4			
8	Providing plug and rod with locking arrangements.	Lump	sum			
	Dismantling existing sluice and removing debris.	Lump	sum			
	Total sluice No. I ...	...	...	...	...	...
	Sluice No. II.	Lump	sum			
	Waste Weir.					
1	Earthwork excavation	C.yds.	451			
2	Concrete in surki motar	C.ft.	2,067			
3	Burnt brick in surki mortar	,,	7,266			
4	Burnt stone slabs 6" thick dressed ...	S.ft.	982			
5	Surki mortar plastering	Sqr.	31·5			
6	New stone work	C.yds.	659			
7	Filling bolders in deep pits	C.yds.	458			
8	Unforeseen charges	Lump	sum			
	Total for Weir ...	..	...	...	...	...
	Total Bund, Sluices and Weir ...	...	...	...	...	...
	Contingencies at 5 % ...	...	...	...	...	...
	Grand Total ...	...	..	...	...	...

Notice dated 24th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 19th February 1929, for restoring Chikbandehalli Thangadikunte Tank, Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and eighty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Chikbandehalli Thangadikunte, Mulbagal Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will be rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Chikbandahalli Tangadikunte, Mulbagal Taluk, Reg. No. 39.

Items of work	Per	Quantity	Rate	Cost	Total
Bund.			Rs.	Rs.	Rs.
Earthwork to bund watering and tamping including lead and lift R. L. 55·00.	C.yds.	4,237			
Turfing to bund	S.yds.	3,511			
Removing and resetting old stone work ...	C.yds.	379			
New stone work	,,	703			
Fixing grade stones cutting figures and painting, etc., complete.	No.	12			
Index stones	,,	12			
Register No. stone	,,	1			
Gauge stone	,,	1			
B. M. stones	,,	2			
Date stone	,,	1			
Jungle clearing and cutting trees and removing roots.	Lump	sum			
Total to Bund ...	...	...	...	...	...
Sluice at R. L. 44·00.					
Earthwork	C.yds.	30			
Refilling the bund with watering and tamping	,,	30			
Surki concrete for foundation	C.ft.	158			
Burnt brick in surki mortar	,,	249			
Burnt stone slabs 4" to 6" thick	S.ft.	136			
Plastering with surki mortar	Sqrs.	4·12			
Providing wooden plug and rod with locking arrangements.	Lump	sum			
Cutting holes in orifice slab	Lump	sum			
Dismantling old sluice and removing debris ...	Lump	sum			
Total for Sluice ...	...	...	...	...	...

Items of work	Per	Quantity	Rate	Cost	Total
Weir.					
Earthwork excavation for body wall and return	C.yds.	41			
Surki concrete for foundation	C.ft.	86			
Burnt brick in surki mortar	,,	316			
Burnt stone slabs, 4" to 6" thick	S.ft.	225			
Plastering with surki mortar	Sqrs.	3·25			
Rough stone work for apron	C.yds.	100			
Joggle joints	Each	8			
Total for Weir ..	...	..	..	...	...
Total of Bund, Sluice and Weir ...	...	...	...	...	...
Contingencies ...	...	...	..	...	...
Grand Total ...	...	...	...	...	...

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 17th January 1929, Part VI, pages 68-70, calling for tenders for restoring Talakunte Kondlakere and Talakunte Rayarakere, Malur Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 17th January 1929, Part VI, pages 70-72, calling for tenders for restoring Chikpayalgurki Tank Regd. No. 137, Chikballapur Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 17th January 1929, Part VI, pages 67-68, calling for tenders for constructing a new tank across Vrishabavati near Kamasamudram, Bowringpet Taluk. Last date of tender is 2 P.M. on 4th February 1929.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 17th January 1929, Part VI, pages 72-75, calling for tenders for constructing a new Thippaganahalli Tank, Goribidnur Taluk. Last date of tender is 4th February 1929, at 2 P.M.

Dated 24th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive-Engineer, Kolar Division, up to 2 P.M. of 19th February 1929, for Restoring Pare Hosahalli Tank, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Pare Hosahalli Tank, Kolar Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason what ever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate for restoring Pare Hosahalli Doddakere Register No. 64—793 of Kolar Taluk.

Items of work	Per	Quantity	Rate	Cost	Total
BUND.			Rs. a. p.	Rs.	
Earthwork to bund including watering and tamping with lead and lift.	C.yds.	23,828	...		
Turfing to bund	S.yds.	9,696	..		
Puddle wall	C.yds.	650	..		
Removing and resetting old stone with new jelly.	,,	640	...		
New stone work for revetment	,,	3,079	...		
Providing new grade stones, chiselling and painting.	No.	36	...		
Do do Index stones ...	,,	36	...		
Do do B. M. stones ...	,,	2	...		
Do do Gauge stone ...	,,	1	..		
Date and Rigister No. stone	,,	1	..		
Removing jungle on bund	Grade	30	...		
Total of bund ...	...	...	...	...	...

Items of work	Per	Quantity	Rate	Cost	Total
SLUICE No. 1.			Rs. a. p.	Rs.	
Earthwork cut opening the bund ...	C.yds.	71			
Refilling the same	,,	78			
Surki concrete	C.ft.	118			
Burnt brick in surki mortar	,,	535			
Burnt stone slabs 4" to 6" thick dressed ...	S.ft.	226			
Surki mortar plastering	Sqrs.	8·46			
Providing plug and rod with ocking arrangements.	Lump	sum			
Drilling holes in orifice slabs	Lump	sum			
Total of sluice No. 1 ...	...	...	...	...	..
Sluice No. II as above ...	...	...	..	....	...
Total for sluices ...	...	..	...	...	...
WASTE WEIR No. 1.					
Earthwork excavation	C.yds.	824			
Surki concrete	C.ft.	948			
Burnt brick in surki mortar	,,	5,260			
Burnt stone slabs 4" to 6" thick dressed ...	Sft.	740			
Surki mortar plastering	Sqrs.	49,85			
New stone work	C.yds.	533			
Earthwork to flank bund	,,	250			
Total of weir No. 1 ...	..	...	...	..	...
WASTE WEIR No. 2.					
Earthwork excavation	C.yds.	35			
Surki concrete	C.ft.	197			
Burnt brick in surki mortar	,,	886			
Burnt stone slabs 4" to 6" thick dressed ...	S.ft.	153			
Surki mortar plastering	Sqrs.	12·42			
New stone work	C.yds.	133			
Joggle joints fixed in surki mortar, etc., complete.	No.	74			
Total of weir No. 2 ...	...	...	...	...	...
Total of bund, sluice and waste weirs ...	...	...	...	...	...
Contingencies	...	...	...	...	...
Grand Total ...	...	...	...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to notification calling for tenders for constructing a Travellers' Bungalow at Pavagada. Last date of submission of tenders is 2nd February 1929.

V. V. PATANKAR,
Executive Engineer,